

Analysis of Grouted Splice Sleeve Connection in Precast Column to Column Joint

Prof. R. M. Puranik¹, Dr. R. S. Tatwawadi²

¹Assitant Professor, Civil Engineering Department, Jawaharlal Darda Institute of Engineering and Technology, Yavatmal, 445001, Maharashtra, India.

² Principal, Jawaharlal Darda Institute of Engineering and Technology, Yavatmal, 445001, Maharashtra, India.

¹rujit_puranik@jdiet.ac.in, ²principal@jdiet.ac.in

Abstract

In present scenario, Precast construction is replacing RCC structures in most of the locations all over the world. Economical and speedy construction is significance of precast structures. The primary objective of this research is to evaluate the stresses generated throughout the joint section . When the stresses are calculated, the reduction of section size or approach for economical design is possible. Results of stress analysis concerning the axial load in the form of pressure applied on column to column precast structure is assessed using finite element software i.e. ABAQUS. The connection maintained between two precast columns is executed by grouted splice sleeve and acts as a joint. The column has the cross section with both the sides 500mm and with the length of 4150mm. The longitudinal reinforcements bars protruding throughout both columns are 20mm diameter bars. obtain The performance of grouted splice sleeve is observed and stresses d in grout, grout sleeve steel and rebar connection both columns are obtained. The structure is divided in to finite parts and nodes using ABAQUS. The stresses every part of structure under certain pressure can be visible in visualisation at every node or instance of ABAQUS. Comparison of precast columns and a single RCC column is observed. The stresses developed and performance of model is visualised in this study. But the location of maximum stresses developed are seen to be varied in both the cases.

Introduction

In precast construction the joint between two structural elements plays a significant role in increasing the strength of structure. In this thesis the approach is to join the two precast column elements with splice using grouted sleeve. The term grouted splice sleeve contains of a hollow steel pipe and is grouted with high strength concrete. The rebar which connects two column elements will pass through the grouted sleeve and connects two columns is known to be splice. For gaining the strength of two prefabricated elements appropriate connection is required which is provided by grouted splice joint in column segments. Bond strength between grout and splice plays the important role in connection between the two precast segments. There is always a major disadvantage in cast insitu reinforced concrete

construction (RCC) i.e, the onsite condition should be favourable for construction. The onsite conditions play a vital role in construction purpose. This could affect the quality and strength of RCC construction. The time consumed in RCC construction is more than precast construction, thus increases the cost of construction. To overcome these conditions precast construction are preferred. The structural elements are formed in the factory and then elements are assembled on site. Due to this process the speed of construction increases. The quality and strength of structural elements is maintained to greater extent. Instead of large sections of RCC structural elements, small precast sections can be assembled resulting in faster construction process.

Feasibility of grout in precast connections

The column to column connection is being tested by axial tension, shear test, four point bending with and without axial compression. The connection between two columns is in the form of grouted splice sleeve. The stress carried by the splice transfer from one column to another in tension failure test is viewed. Damage is developed in interface between two column units. The significance stress transfer in splice region is the important factor in this experiment. Due to these tests' failure took place in joint section of column. The direct tension test specified the effectiveness of the stress transfer along the splice region. Failure took place far from the joint section, outside the bar splice region or grout rebar region. Evaluation of bond strength of reinforcing bars is carried out to investigate the feasibility of utilizing a generic grout- filled reinforcing bar splice. Lap splice specimens and butt-splice specimens were tested with different confining steel within the grout filled steel pipe. High bond strength of reinforcing bars can be achieved by confining the grout surrounding the bars. Different characteristics of grout can be tested in the grout filled steel pipes to investigate the performance of the structure with respect to axial loads in further investigations.

Stress evaluation using ABAQUS

A formulation with concrete damage plasticity was implemented in ABAQUS code to evaluate the steel-concrete composite behaviour under monotonic loads. Then non-linear numerical investigation of beam column joint is performed in ABAQUS for observing stresses and strain the particular portion of joint. Beam-column connection is done by a mechanical joint, that contains structural elements like threaded re-bars, nuts, couplers, and anchor re-bars. Modelling techniques to calculate stress and strain in ABAQUS used are:

- Nonlinear stress-strain relationship of unconfined and confined concrete under multi-axial stress conditions.
- Concrete damaged plasticity model

- Mesh discretization, mesh density, mesh compatibility, and element distortion
- Modelling of embedded elements
- Modelling of contact elements
- Assigning material properties

Before proceeding towards actual simulation of Precast two column segments, the experimental analysis on grout-filled splice performed by Amin Einea is being simulated using ABAQUS and the results are compared in following validation. The rebar splice grouted sleeve is tested under axial loading to investigate the failure of grouted sleeve. The same test is performed in ABAQUS under the Pressure of 86.11 KN/mm^2 . This model shows the placement of rebars, boundary conditions applied at the bottom of the sleeve and pressure applied on the model. The visual high pressure effects confirmation is observed in the mid-section of a grouted sleeve.

The reliable design of beam column joints can be performed through non linear finite element analysis. In this study, replacement of RCC in situ construction with small precast segments for safe and economic design is performed. Grouted splice sleeve can be used between column to column joint to increase the strength of precast segments. To evaluate the stresses obtained in the grouted splice sleeve due to axial compression load in column. This can be achieved by calculating the stresses at critical section of precast joint by using the Abaqus software (finite element analysis).

Investigation

The precast column to column joint is designed in ABAQUS i.e., finite element software for checking the stresses in grout and rebar connection of two columns. After investigating the stresses, the precast structure will be compared with RCC monolithic column by applying same load to the appropriate structure

Specification

Precast column elements consist of cross section 500×500 and length of column is 4150mm. Four Grout pipes which has diameter of 63mm and grout diameter is 58mm. The length of pipe is 1000mm. Four 20mm Rebars are passing through grout from one column to another column. The length of rebar is 2000mm. It acts as a wire. 8 reinforcements @20mm passing in precast column units acts as a wire. Stirrups @8mm acts as a wire. Steel beam consist of cross section 500×500 and length of 2000mm. Precast joint consists of cross section 500×500 and length is 20mm. Load applied is 2500KN.




Figure 0:1 Orientation of column




Figure 0:2 Load Applied on column surface

Meshing Technique

The significance of Mesh module is to generate the finite element mesh. The meshing technique that ABAQUS will use to create the mesh, the element shape, and the element type. ABAQUS uses a number of different meshing techniques. The default meshing technique assigned to the model is indicated by the colour of the model when you enter the Mesh module. The size of mesh can be controlled manually, it depends upon the approximation of the data we have to obtain.

After meshing the part, if the changes are made in assembly of module then it will affect

themeshing of module. The parts in which changes are happened, those parts will have to meshonce again.

In this study, for all the parts auto meshing is performed. Meshing of grout pipe, grout insidethe pipe and grout rebar are important factors in the module. Due to meshing, the calculationofstressesatnodesarecalculated.




Figure 0:3Meshing of Grout pipe

Results & Discussion

Visualization

After completing the job, all the output of the design is observed in the Visualization module. The use of Visualization module to read the output database that ABAQUS generated during the analysis and to view the results of the analysis.

In this study, simulation of stresses is performed to investigate the stresses throughout the joint in precast column structure. But the stresses generated in column model is also an important factor to observe the variation of stresses developed in both precast and RCC structure.

Because of connection of two column units in Precast model, the stresses generated in this structure is greater than RCC structure. The accuracy of output data in precast model is greater because

use of auto meshing the model, there was increase in the meshes developed in the two column units. Greater amount of stresses is developed in joint section and where the beam is tied to column. In visualization model, the maximum amount of stresses developed in all over the structure is 188.4 N/mm^2 shown below:




Figure 0:1Stresses in model

In RCC column model, the column is monolithic. There are no joints connecting the column units, so the stresses developed in this model is at column beam joint, reinforcements and at the end of column. The stresses developed are less as compared to precast model because there is only one column unit. The approximation is more in RCC model. The amount of meshes are less and the nodes are less, therefore, the variation of stresses throughout the RCC model differs. In Visualisation model, the maximum amount of stresses developed in all over the structure is specified in left corner of the figure shown below:




Figure 0:2 Stress in RCC

The maximum stresses developed due to axial compressive load on column are on main reinforcement bar of RCC section. The maximum stress developed is 102.6 N/mm^2 . In the mid-section of RCC column stresses developed are varying around 85 N/mm^2 to 90 N/mm^2 .


Stress variation in joint section

Joint section consists of three parameters: grout pipe which has material steel, grout consists of higher concrete grade i.e. M80 and grout rebar. Due to axial load applied on the column, stresses generated in joint section are visualised in ABAQUS. The column section will try to buckle and the grout pipes subjected to tension will generate more stresses as compared to grout pipe subjected to compression. The stresses developed in finite element analysis software ABAQUS are observed in output file. Output file shows at which nodes the stresses, displacement, forces, moments etc, are developed. In this study we have selected the part of which the stresses are to be investigated. The example of selection of part in which stresses are evaluated is shown in figure below. The stresses are generated in the steel pipe, grout rebar (steel), and grout M80 in grouted splices. Under the axial compressive load, as shown in table no.1. Total amount of four grout sleeves are analyzed situated between precast column segments.

Table 0-1 Maximum Stresses developed in Joint section

Part	Material	Yield Strength (N/mm ²)	Total nodes	Node no.	Maximum Stresses (N/mm ²)
GroutPipe1	Steel	250	6027	2128	102.233
GroutPipe2				2128	101.96
GroutPipe3				2128	118.919
GroutPipe4				2128	120.024
Grout inPipe1	Grout	80	4530	1357	25.452
Grout inPipe 2				3025	21.284
Grout inPipe 3				3180	21.281
Grout inPipe 4				1357	25.512
Groutrebar1	Steel	250	201	100	122.088
Groutrebar1				100	121.696
Groutrebar1				100	137.174
Groutrebar1				100	136.926

Comparison of stresses developed in four grout rebar:



The highest stress developed due to loading is less than the material's yield strength

1. Highest stress developed in grout pipe steel material = $120.024 \text{ N/mm}^2 < 250 \text{ N/mm}^2$.
2. Highest stress developed in the grout M80 = $25.512 \text{ N/mm}^2 < 80 \text{ N/mm}^2$.
3. Highest stress developed in grout rebar = $137.17 \text{ N/mm}^2 < 250 \text{ N/mm}^2$.

Conclusion

Evaluation of Stresses using ABAQUS (Finite element analysis software) is proven to be accessible and a handy technique. At any section or location of structural segments, the stresses are easily analyzed with this technique.

From this study, particular conclusions can be made:

- Maximum stress generated in Precast column segments is 188.4 N/mm^2 .
- Maximum stress generated in RCC column section is 102.6 N/mm^2 .
- The stresses generated in precast model is greater than stresses generated in RCC model.
- The higher amount of stresses are generated in Precast model, because the column is divided into two segments, but still it is safe as the stresses developed are below the yield strength of material.
- The precast segment connections can be further analyzed by lowering the grade of grout from M80 to M60.

References

1. Nerio Tullini, Fabio Minghini (2016). Grouted sleeve connections used in precast reinforced concrete construction—Experimental investigation of a column-to-column joint. *Engineering Structures* 127(2016)784-803.
2. Amin Einea, Takashi Yamane, Maher K. Tadros (1995). Grout-Filled Pipe Splices for Precast Concrete Construction. *PCI Journal*.
3. Suveet.B.Jain, Nitin Naik, Madhu Andelimath, Vinay.S.Hosagoudar, Manasa H.G. Use of Mechanical Threaded Coupler in Steel Reinforcement.
4. G. Metelli, P. Riva. Behaviour of beam to column dry joint for precast concrete column
5. G. Vlassis, C. C. Spyrakos & S. Tsoukantas. Seismic analysis and design of a precast concrete framed structure.
6. Ravikanth Chittiprolu, Ramancharla Pradeep Kumar. Seismic safety of joints in precast buildings—A safety of the art literature review.
7. J.D. Nzabonimpa, Won-Kee Hong, Jisoon Kim. Non-Linear finite element model for novel mechanical beam column joints for precast concrete based frames.
8. R Park. The Fib state-of-the-art report on the seismic design of precast concrete building structures.

9. A.Alias,F.Sapawi,A.Kusbiantoro,M.A.Zubir¹andA.B.AbdRahman.Performanceofgrouted splicesleeve connectorundertensileload.
10. IzniSyahrizal Ibrahim, Khairul HazmanPadil, Hamid Mansoor Ali Bady, AbdulAziz Saim, Noor Nabilah Sarbini. Ultimate shear capacity and failure of shear keyconnectioninprecastconcreteconnection.